



△ SPECIFICATION

Current Rating: 12 Amp/Way Max.
 Voltage Rating: 300V AC
 Withstanding Voltage: 2500V AC (1 Minute)
 Test Time = 60s/1 PCS
 Operation Temperature: $-40^{\circ}\text{C} \sim +105^{\circ}\text{C}$
 Soldering Reliability: Test Temperature = $250^{\circ}\text{C} \pm 10^{\circ}\text{C}$
 5 Seconds Max.
 Solder Pin: Copper Alloy, Tin Plated
 Insulator Body: Polyamide + G.F. (UL94V-0), Green
 RoHS Compliant

4UCON 元化興業股份有限公司
 4UCON TECHNOLOGY INC.

DRAWING No. **07559**

APPROVED BY MEI
 CHECKED BY HZF
 DRAWING BY CYP

UNLESS OTHERWISE SPECIFIED TOLERANCES ARE
 X. ± 0.50
 .X ± 0.30
 .XX ± 0.20
 ANG. $\pm 1^{\circ}$

SCALE NONE

REV. A2

UNIT mm

| | | | | |
|------|------|-------------|-----|------------|
| NO. | REV. | REVISIONS | CHK | DATE |
| △ A2 | | Modify Data | HZF | 01/30/2016 |
| △ A1 | | Modify Data | HZF | 08/14/2012 |
| △ A0 | | NEW RELEASE | HZF | 04/10/2009 |