



**SPECIFICATION**  
 Current Rating: 60 Amp/Way Max.  
 Voltage Rating: 300V AC  
 Withstanding Voltage: 2500V AC (1 Minute)  
 Test Time = 60s/1 PCS  
 Operation Temperature: -40°C ~ +105°C  
 Soldering Reliability: Test Temperature: 250°C ± 10°C / 5s Max.  
 Insulator Body (Housing): Polyamide + G.F. (UL94V-0)  
 Solder Pin: Copper Alloy, Tin Plated  
 RoHS Compliant

**4UCON** 元化興業股份有限公司  
 4UCON TECHNOLOGY INC.

DRAWING No.		APPROVED BY		UNLESS OTHERWISE SPECIFIED TOLERANCES ARE X. ±0.50 .X ±0.30 .XX ±0.20 ANG. ±1°
21509		MEI		
		CHECKED BY HZF		
		DRAWING BY CYP		
SCALE	NONE	REV.	A0	UNIT mm

NO.	REV.	REVISIONS	CHK	DATE
△ A0		NEW RELEASE	HZF	06/07/2018