


**SPECIFICATION**

Contact Resistance: 3 Ohms Max.  
 Insulation Resistance: 5 Megaohms Min.  
 DC 300V/10ms  
 100% Open/Short/Intermittence Test  
 RoHS Compliant



Pin Assignment	
P1	P2
1	1
2	2
3	3
·	·
·	·
·	·
·	·
37	37
38	38
39	39
40	40

No.	Name	Q'ty	Description
①	Wire	---	UL2678,PH0.635mm 40P Gray Flat Cable,PVC 30AWG(7*0.102TC) With Red Line
②	Connector	2Pcs	1.27X1.27mm IDC Socket Without SR,40Pin,Black

**4UCON** 元化興業股份有限公司  
 4UCON TECHNOLOGY INC.

DRAWING No.		APPROVED BY		UNLESS OTHERWISE SPECIFIED TOLERANCES ARE .X ±0.5 ANG. ±0.5°
22571		MEI		
		CHECKED BY		
		HZF		
DRAWING BY		LZX		
SCALE	NONE	REV.	A0	UNIT mm

△ A0	NEW RELEASE	HZF	08/30/2023
NO.REV.	REVISIONS	CHK	DATE